



NamPower Transmission Master Plan

Presentation to AEDU Namibia

NamPower | March 2019

Content


Outline

- Background
- Demand and Supply
- Backbone – now and future
- Summary and timelines


Background

- Annual update of Transmission Master Plan Development
 - Based on updated peak demand load forecast / generation scenarios
 - Update the transmission infrastructure requirements
 - Establish changes / additions to previous Master Plans
 - Study period 2019 – 2023
- Proposed new developments are included in the Transmission Capex budget submission

Maximum Peak Demand Load Forecast



Namibian Electricity Load Forecast 2018- 2042
(Including System Losses)



Existing Generation and Imports



Generation scenarios

Generation / Source	MW
Ruacana	347
Van Eck	10
Anixas	22.5
ZPC, Zimbabwe	80
ZESCO, Zambia	50
REFIT Programme	14 plants (PV, wind) of which 3 still outstanding Each limited to 5 MW Total 70 MW
Omburu PV, Omburu	4.5
Greenam	20
Hardap PV	37
ESKOM, South Africa	200MW firm and 300MW non-firm

New Generation beyond 2020



Generation scenarios

Generation / Source	MW
* Diaz Wind Farm, Lüderitz	44
* Otjikoto Biomass	40
New Wind	(40 + 50) = 90
New PV	(20 + 20) = 40
New Firm Generation	50
Baynes Hydro Power Plant, Kunene region	300

Backbone Network Studies



- Backbone network development are planned to meet the capacity requirements for load growth, generation options, security of supply, system stability, system reliability and wheeling.
- Adherence to Grid Code compliance by resolving both substation and line deviations.
- Determine new network infrastructure requirements to sustain and allow future load demand growth
- Determine new network infrastructure requirements to integrate new generation (NamPower and IPPs)

Backbone Network Projects



Approved projects:

- Auas – Gerus 400kV
- Auas – Kokerboom 2nd 400kV
- Obib – Oranjemond 400kV / 220kV

Budgetary provision required for recommended projects:

- Otjikoto – Masivi 220kV
- Erongo 220/66kV 90MVA substation

Summary – NamPower Initiated



Project name	Expected completion / commissioning dates				
	2019	2020	2021	2022	2023
Ruacana-Hippo 330 kV					
Ohama 132/33 kV, 20 MVA Trfr including in/out arrangement					
Kunene-Omatando 400 kV project					
Omatando 132/66 kV transformers					
Okanya-Okatope feeder bay					
Masivi & Shiyambi substations, Masivi DVSD					
Rundu 132/11 kV 40 MVA Trfr					
Otjikoto – Masivi 220 kV Line					
Erongo 220/66 kV 90 MVA substation					
Brakwater substation					
Leutwein 66/22 kV, 5 MVA substation upgrade					
Auas-Gerus 400 kV					
Auas-Kokerboom 2 nd 400 kV line					
Nabas 5 MVA transformer					
Warmbad substation					
Khurub-Aussenkehr 132 kV					
Obib-Oranjemond 400 kV / 220 kV					

Summary – Customer Initiated



Project name	Expected completion / commissioning dates					
	2019	2020	2021	2022	2023	
Calueque Pumping 5 MVA substation						
Okapya 66/33 kV 5 MVA Trfr						
Okapya SS with Temp 2.5 MVA Trfr						
Omatando 66/11 kV 20 MVA Trfr						
Rehoboth 132/11 kV, 20 MVA substation						
Otjiwarongo 20 MVA Trfr & upgrade						
Okombahe substation upgrade						
Karibib 66/22 kV 10 MVA Substation						
Lithops 132/33 kV & 3 rd 220/132 kV						
Sekelduin 132/33 kV & 132/66 kV						
Ruby 10 MVA transformer						
Okahandja 20 MVA Trfr & Upgrade						
Okomita Substation (Interim)						
Khomas 220/66 kV substation						
Hardap 3 rd 40 MVA Trfr						





Thank you